



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 22 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cox of Blaik Oil Co. has this

date requested permission to plug the following described well:

Mr. Cox guarantees payment of the plugging fee.

Operator's full Name: Blaik Oil Company

Complete Address: 203 Park Avenue, Oklahoma City, Oklahoma

Lease Name: Sharp Well No. 1

Location: C SE SE Sec. 20 Twp. 34 Rge. 41 (E) (W)

County: Morton Total Depth 5548' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Cox was instructed to plug the well as follows:

8 5/8" to 1444' circulated w/ cement. 4 1/2" to 5547' cemented.

Top perforations 5018' Plug bottom w/ 20 sacks cement

Top of cement 4700' Mud 4700' to 1000'

Spot 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'

Very truly yours,

Edward J. Eubank
Conservation Division Agent