

State of Kansas



FORM - CP-2
Rev. 9-8-64

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 15 1965
3-15-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Barker of Anadarko Prod. Co. has this date requested permission to plug the following described well:

Mr. Barker guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co.

Complete Address: Box 351 Liberal, Kansas

Lease Name: Tucker Well No. # 0 2

Location: C SE NE Sec. 19 Twp. 34 Rge. 41 (E)(W)

County Morton Total Depth 5235' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Barker was instructed to plug the well as follows:

8 5/8"-1527' Circulated w/cement. 5 1/2"-4800' Cemented. Top perforations-4388'

Plug bottom w/35 Sax.cement top cement 4150'. Mud 4150' to 700'

Spotted 35 Sax.cement 700' to 600' Mud 600' to 45'

Plug, Hulls, 15 Sax.cement 45' to 0

Very truly yours,

[Signature]
Conservation Division Agent