

15-129-00411-0000

FORM - CP-2  
Rev. 9-8-64

State of Kansas



JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 9 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Parris of Anadarko Production Co. has this date requested permission to plug the following described well:

Mr. Parris guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co.

Complete Address: Box 351 Liberal, Kansas

Lease Name: Tucker Well No. # 01

Location: C SW NE Sec. 19 Twp. 34 Rge. 41 (E) (W)

County Morton Total Depth 5250' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Parris was instructed to plug the well as follows:

8 5/8"-1492' Circulated w/cement. 5 1/2"-4780' Cemented.

Plug back to 3742' Perforations 3270' to 3271'

Plug bottom w/35 Sax. cement top cement 3000'. Mud 3000' to 700'

Spotted 35 Sax. cement 700' to 600' Mud 600' to 45'

Plug, Halls, 15 Sax. cement 45' to 0

Very truly yours,

Conservation Division Agent