

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 3 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Gatlin of Anadarko Prod. has this

date requested permission to plug the following described well:

Mr. Gatlin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name: Sleeth Well No. 01

Location: C NW SE Sec. 19 Twp. 34 Rge. 42 (W)

County Morton Total Depth 5203' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Gatlin was instructed to plug the well as follows:

8 5/8" to 1516' circulated w/ cement. 5 1/2" to 5135' cemented.

Top perforations 4671' Plug bottom w/ 20 sacks cement.

Top of cement 4400' Mud 4400' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

*E. J. Evers*  
Conservation Division Agent