

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 06 1978

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Radloff of Cities Service Co. has this
date requested permission to plug the following described well:

Mr. Radloff guarantees payment of the plugging fee.

Operator's full Name: Cities Service Company

Complete Address: 3545 N.W. 58th St. Oklahoma City, Okla.

Lease Name: Eagley "A" Well No. 3

Location: 1650' FSL & 330' FWL SW/4 Sec. 11 Twp. 34 Rge. (E)(W) 41

County: Morton Total Depth 5465 ⁵⁴⁷⁵ Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Radloff was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 30 sk cmt plug (15370'-15220') thru
drill pipe. Heavy mud to 2460' set 75 sk cmt plug (2460'-2250') thru
drill pipe. Heavy mud to 1557' set 35 sk cmt plug (1557'-1457')
thru drill pipe. Heavy mud to 34' set solid bridge & 10 sk cmt plug
(34'-4')

Very truly yours,

Leo Massey
Conservation Division Agent