

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 27 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Cook of Panhandle Eastern has this

date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Panhandle Eastern Pipe-Line Company

Complete Address: Box 828, Liberal, Kansas

Lease Name: Barker Well No. 1-24

Location: SW NW SE Sec. 24 Twp. 33 Rge. 41 (X) (W)

County Morton Total Depth 2340' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

7" to 453' circulated w/ cement, 4 1/2" to 2301' cemented

Top perforations 2174' Plug bottom w/ 30 sacks cement.

Top of cement 1800' Mud 1800' to 500'

Spotted 30 sacks cement 500' to 400' Mud 400' to 50'

Plug, Hulls & 10 sacks cement 50' to 0'

Very truly yours,

Edgar J. Eves
Conservation Division Agent