

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Barker of Anadarko Prod.Co. has this

date requested permission to plug the following described well:

Mr. Barker guarantees payment of the plugging fee.

Operator's full Name: Anadarko Prod.Co.

Complete Address: Box 351 Liberal, Kansas

Lease Name: Stewart-Carey Well No. A-1

Location: C SW NE Sec. 30 Twp. 33S Rge. 41 (E) (W)

County Morton Total Depth 5351' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Barker was instructed to plug the well as follows:

8 5/8"-1404' Circulated w/cement.

Mud 5351' to 3205' Spotted 70 Sax.cement 3205' to 2905'

Mud 2905' to 694' Spotted 35 Sax.cement 694' to 575'

Mud 575' to 45' Plug,Hulls,15 Sax.cement 45' to 0

Very truly yours,

Hugh Scott
Conservation Division Agent