

State of Kansas



JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

SEP 1 1965

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Gattin of Anadarko Production Co. has this  
date requested permission to plug the following described well:

Mr. Gattin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co.

Complete Address: Box 351 Liberal, Kansas

Lease Name: Conard Well No. A-2

Location: C SW NE Sec. 19 Twp. 33S Rge. 40 (E) (W)

County Morton Total Depth 5844' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Gattin was instructed to plug the well as follows:

8 5/8" - 1496' Circulated w/cement.

Mud 5844' to 5830' Spotted 20 Sax. cement 5830' to 5750'

Mud 5730' to 5530' Spotted 20 Sax. cement 5530' to 5410'

Mud 5410' to 700' Spotted 35 Sax. cement 700' to 600'

Mud 600' to 45' Plug, Hulls, 15 Sax. Cement 45' to 0

Very truly yours,

[Signature]  
Conservation Division Agent