

15-189-20201

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 5 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Brooks of G-M has this

date requested permission to plug the following described well:

Mr. Brooks guarantees payment of the plugging fee.

Operator's full Name: Graham-Michaelis Corporation

Complete Address: Box 247, Wichita, Kansas

Lease Name: Stalcup Well No. 1-25

Location: C SW SE Sec. 25 Twp. 34 Rge. 36 (E) (W)

County: Stevens Total Depth 6560' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Brooks was instructed to plug the well as follows:

8 5/8" to 1731' circulated w/ cement. Mud 6560' to 2850'


Spot 100 sacks cement 2850' to 2650' Mud 2650' to 1700'

Spot 35 sacks cement 1700' to 1600' Mud 1600' to 400'

Spot 25 sacks cement 400' to 325' Mud 325' to 50'

Plug, Hulls & 10 sacks cement 50' to 0'.

Very truly yours,


Conservation Division Agent