

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 8 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Gearhart of Beren has this

date requested permission to plug the following described well:

Mr. Gearhart guarantees payment of the plugging fee.

Operator's full Name: Beren Corporation

Complete Address: 1130 Vicker KSB&T Bldg., Wichita, Kansas

Lease Name: Lewis Well No. 1-11

Location: 50' E of C NW Sec. 11 Twp. 34 Rge. 36 XX
(E) (W)

County: Stevens Total Depth 6310' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gearhart was instructed to plug the well as follows:

8 5/8" to 1727' circulated w/ cement. Mud 6310' to 2950'

Spot 100 Sacks cement 2950' to 2600' Mud 2600' to 1100'

Spot 35 sacks cement 1100' to 1000' Mud 1000' to 45'

Plug, Hulls " 15 sacks cement 45' to 0'.

Very truly yours,

Edward J. Lewis
Conservation Division Agent