

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 17 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Bovaird has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Bovaird Supply Co.

Complete Address: 525 S. Western, Liberal, Kansas

Lease Name: Loether Well No. 1

Location: C NE SE Sec. 14 Twp. 34 Rge. 37 XX (E) (W)

County: STEVENS ~~ORTON~~ Total Depth 6815' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 1775' circulated w/ cement. 4 1/2" to 6815' cemented.

Top perforations 6362' Plug bottom w/ 20 sacks cement.

Top of cement 6100' Mud 6100' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent