

020124

REGISTRATION COMMISSION
OIL DIVISION - PLUGGING SECTION
1000 DERBY BUILDING
DODGE CITY, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

3-2-88
Docket # WE-16,786
API NUMBER 15-Drill Completion Date 5/21/64
C NE SW, SEC. 12, T. 34 S, R. 33 W/4
1980 feet from S section line
3300 feet from E section line
Lease Name Condit Unit Well # 1-1
County Seward
Well Total Depth 6384 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1599

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SKD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargents Casing Pulling Service License Number 6547

Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 7 p.m. Day: 9 Month: 2 Year: 1988

Plugging proposal received from Doug Blair

(company name) Sargents Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 6380' PBTD 6333' Perfs at 6255-69' Elevation 2830' GL

1st plug pump 2 sx hulls and 25 sx cement to bottom,

2nd plug run 30 sx cement at 2210',

3rd plug pump 50 sx cement at 1640',

4th plug pump 25 sx cement at 700', 5th plug pump 10 sx cement at 0-40'.

Plugging Proposal Received by Glen Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 2 Month: 3 Year: 1988

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement to bottom,

2nd plug pumped 30 sx cement at 2210',

3rd plug pumped 50 sx cement at 1640',

4th plug pumped 25 sx cement at 700',

5th plug pumped 10 sx cement at 0-40',

Remarks: Used common cement by Sargents. Recovered 2225' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed: Glen Barlow
(TECHNICIAN)