

To: 1 020126
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Docket #E-16,786

NW SE, SEC. 12, T. 34 S, R. 33 W/8X

1980 feet from S section line

1980 feet from E section line

Lease Name Condit Unit Well # 2-1

County Seward

Well Total Depth 6325 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1616

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Operator: Anadarko Petroleum Corporation

Name & Address P.O. Box 351

Liberal, KS 67905-0351

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 4 p.m. Day: 7 Month: 3 Year: 19 88

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling (phone) 316-624-7455

logs: 4 1/2" at 6324' PBD 5910' (CIBP) Perfs at 5963-91, 6254-57'

1st plug pump 2 sx hulls and 25 sx cement to bottom.

2nd plug pump 30 sx cement at 2470', 3rd plug pump 50 sx cement at 1630',

4th plug pump 25 sx cement at 650', 5th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 10 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement to bottom.

Pressured to 900 lbs. on 3/7/88.

2nd plug pumped 30 sx cement at 2470',

3rd plug pumped 50 sx cement at 1630',

4th plug pumped 25 sx cement at 650',

5th plug pumped 10 sx cement at 40-0'.

Remarks: Used common cement by Sargent's. Recovered 2474' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

I (did /~~xxxxxx~~) observe this plugging.

Signed Glenn Barlow
(TECHNICIAN)