

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-02296-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 23-11S-19W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: DEVINE R P Well #: 1
County: ELLIS Total Vertical Depth: 3464 feet

Operator License No.: 34938
Op Name: ARGENT ENERGY (US) HOLDINGS, INC
Address: 2 HOUSTON CENTER 909 FANNIN ST.
HOUSTON, TX 77010

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	13	127		175 sx
PROD	5	3447	1690	300 SX
SURF	13	1308		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/25/2015 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DEAN HASELHORST Company: ARGENT ENERGY INC. Phone: (785) 650-9787

Proposed Plugging Method: Ordered 475 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Perforations: 2913' - 3464'

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/25/2015 5:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Excell Wireline Service set CIBP at 2810'. Topped with 5 sx cement. Shot casing at 1690'. Pulled 6' sub. Rigged to casing and pumped 125 sx cement w/200 # hulls mixed in. Pulled casing to 1300' and pumped 50 sx cement w/100 # hulls mixed in. Pulled casing to 600' and pumped 100 sx cement w/100 # hulls mixed in. Pulled casing to 250' and pumped 50 sx cement to circulate cement to surface. Pulled casing to surface. Hole standing full.

GPS: 39.08713 -099.39678
4832' FSL 2411' FEL
SW NW NW NE

Perfs:


Top	Bot	Thru	Comments
3447	3464		

Remarks: QUALITY WELL SERVICE INC.

Plugged through: CSG

District: 04

Signed _____


(TECHNICIAN)

MAR 25 2015

CM

KCC WICHITA

MAR 18 2015

RECEIVED

MAR 02 2015