

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-20266-00-00
Spot: N2NESW Sec/Twnshp/Rge: 22-10S-25W
2310 feet from S Section Line, 3300 feet from E Section Line
Lease Name: BRUNGARDT A Well #: 1
County: GRAHAM Total Vertical Depth: 4080 feet

Operator License No.: 5364
Op Name: BEREN CORPORATION
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4079		125 SX
SURF	8.625	207		175 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/05/2015 11:30 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: BEEN CORP Company: BEREXCO LLC Phone: (316) 772-8649

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: 3815' - 3821', 3848' - 3850', 3860' - 3863', 3897' - 3903', 3954' - 3958', 3976' - 3979', 3993' - 3999', 4015' - 4021'.
Squeezed from 1253' - 1401' w/135 sx cement, 1521' - 1581' w/85 sx cement, 1826' - 1857' w/60 sx cement, 1894' - 1915' w/185 sx cement, 2896' - 3433' w/300 sx cement, 3292' - 3321' w/250 sx cement.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/05/2015 3:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran tubing to 3900' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 3109' and pumped 75 sx cement w/150 # hulls. Pulled tubing to 2124' and pumped 135 sx cement. Good circulation of cement. Pulled tubing out and topped off with 25 sx cement full. Tied on to backside and squeezed with 50 sx cement. Shut in pressure 100 psi.


GPS: 39.16732 -100.10093

Remarks: QUALITY CEMENT TICKET # 6342

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

MAR 25 2015 *CKM*

MAR 09 2015

KCC WICHITA

MAR 18 2015

RECEIVED

Form CP-2/3