

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-02522-00-00  
Spot: N2SESENE Sec/Twnshp/Rge: 23-12S-18W  
3090 feet from S Section Line, 330 feet from E Section Line  
Lease Name: STACKHOUSE OLD Well #: 4  
County: ELLIS Total Vertical Depth: 3675 feet

Operator License No.: 6931  
Op Name: BOWMAN OIL COMPANY, A GENERAL  
Address: 805 CODELL RD  
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3665		100 SX
SURF	8.625	119		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/06/2015 9:00 AM  
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: DONALD A. BOWMAN Company: BOWMAN OIL COMPANY, A GENE Phone: (785) 434-2286

Proposed Plugging Method: Ordered 285 sx 60/40 pozmix 4% gel cement, 13 sx gel and 500 # hulls.  
Perforations: 3424' - 3429', 3451' - 3453', 3474' - 3479' and 3486' - 3488'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/06/2015 1:30 PM KCC Agent: PAT STAAB

**Actual Plugging Report:**

L-K Wireline perforated at 1850', 1407' and 853'. Bowman Oil Co ran in hole with tubing to 3400'. Allied rigged to tubing and mixed and pumped 13 sx gel followed by 50 sx cement w/250 # hulls mixed in. Pulled tubing to 1850'. Allied rigged to tubing and pumped 130 sx cement w/250 # hulls to circulate cement to surface. Pulled tubing. Topped off 5 1/2" casing with 50 sx cement. Hole standing full. Rigged to 8 5/8" casing and pumped 20 sx cement to pressure with 150 psi. Shut in pressure 150 psi.

GPS: 38.99537 -099.28035  
3039' FSL 324' FEL  
NE SE SE NE

**Perfs:**

Top	Bot	Thru	Comments
3486	3488		
3474	3479		
3451	3453		
3424	3429		


Remarks: ALLIED CEMENTING CO TICKET # 055645

Plugged through: TBG

MAR 25 2015 *oxm*

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

*oxm*

KCC WICHITA

MAR 18 2015

RECEIVED

MAR 09 2015