

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-023-20297-00-00
Spot: SWSENE Sec/Twnshp/Rge: 16-2S-42W
2970 feet from S Section Line, 990 feet from E Section Line
Lease Name: MOORE 374 Well #: 16-8-1
County: CHEYENNE Total Vertical Depth: 1844 feet

Operator License No.: 35011
Op Name: CAERUS WASHCO LLC
Address: 600 17TH STREET SUITE 1600N
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1794		70 SX
SURF	7	306		0 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/10/2015 9:00 AM
Plug Co. License No.: 8273 Plug Co. Name: EXCELL SERVICES, LLC
Proposal Rcvd. from: CHUCK SPRAGUE Company: CAERUS Phone: (970) 630-0214

Proposed Plugging Method: Ordered 50 sx common cement yielding 1.32 cu/ft/sx.
7" surface casing set at 306' w/274 sx cement. 4 1/2" production casing set at 1794' w/70 sx cement. TD 1844'.
Perforations: 1675' - 1709'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/10/2015 3:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Set CIBP at 1650'. Dumped 2 sx cement on top with dump bailer. Pressure casing to 250 psi. Perforated production casing at 350'. Pumped 25 sx cement and displaced with 3 barrels of water. WOC for 2 1/2 hours. Tagged cement at 250'. Perforated production casing at 50'. Pumped 11 sx cement. CWC from 7" surface casing. Both casings full.

GPS: 39.87966N -102.03298W

Perfs:

Top	Bot	Thru	Comments
1675	1709		

Remarks: EXCELL SERVICES PROVIDED CEMENT AND PUMP

Plugged through: CSG

MAR 25 2015_{CKM}

District: 04

Signed Darrel Dipman

(TECHNICIAN)

CM

KCC WICHITA

Form CP-2/3

MAR 18 2015

RECEIVED

FEB 25 2015