

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-20204-00-01
Spot: N2NENE Sec/Twnshp/Rge: 26-31S-18W
547 feet from N Section Line, 493 feet from E Section Line
Lease Name: BOISSEAU Well #: 1
County: COMANCHE Total Vertical Depth: 5132 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4906		WITH 2 SX CMT
CIBP		5050		
PROD 4.5		5131	1562	WITH 125 SX CMT
SURF 8.625		497		WITH 500 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/25/2015 12:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4906' WITH 2 SX CMT. PLUG AT 1060' WITH 15 SX GEL & 50 SX CMT. PLUG AT 540' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/25/2015 3:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4906' WITH 2 SX CMT. 1ST PLUG AT 1074' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 537' WITH 50 SX CMT. 3RD PLUG AT 63' WITH 25 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4956	4958		

Received
KANSAS CORPORATION COMMISSION
MAR 12 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

MAR 25 2015 *ekm*

District: 01

Signed

[Signature]
(TECHNICIAN)

[Signature]

RECEIVED
FEB 26 2015
KCC DODGE CITY *[Signature]*