

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20298-00-00  
Spot: NESW Sec/Twnshp/Rge: 16-24S-40W  
1980 feet from S Section Line, 1980 feet from W Section Line  
Lease Name: OVERTON Well #: 1-16  
County: HAMILTON Total Vertical Depth: 2450 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2440	0	WITH 550 SX CMT
SURF	8.625	357		WITH 300 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/27/2015 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 90 SX CMT WITH 150# HULLS. DISPLACE TO 800' WITH WATER. RUN CBL TO DETERMINE TOC. PERFORATE AND/OR RUN TBG AS REQUIRED.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/27/2015 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 90 SX CMT WITH 150# HULLS DOWN 4 1/2" CASING TO 2331'. DISPLACE WITH WATER TO 950'. PRESSURE TO 500# & HOLDING. RUN CBL FROM 850' TO 0'. TOC ABOVE 100'. RUN TBG TO 620' & CIRCULATE CMT TO SURFACE WITH 50 SX CMT. TOOH & TOP OFF WITH 12 SX CMT. PUMP 25 SX CMT DOWN THE ANNULUS TO 250#.

Perfs:

Received  
KANSAS CORPORATION COMMISSION  
MAR 19 2015  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed

*Ken Jehlik*  
(TECHNICIAN)

MAR 25 2015 *exm*

*JA*

RECEIVED  
MAR 10 2015  
KCC DODGE CITY

*RP*