

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-21086-00-01
Spot: W2SWNE Sec/Twnshp/Rge: 18-31S-35W
3329 feet from S Section Line, 2043 feet from E Section Line
Lease Name: OG HINSHAW Well #: 1-18
County: STEVENS Total Vertical Depth: 6230 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5500		WITH 2 SX CMT
PROD	5.5	6230	1800	WITH 350 SX CMT
SURF	8.625	1750		WITH 740 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/03/2015 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STEVE EMICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: SET CIBP @ 5500' WITH 2 SX CMT. PLUG AT 1780' WITH 15 SX GEL & 50 SX CMT. PLUG AT 450' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/03/2015 11:00 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5500' WITH 2 SX CMT. 1ST PLUG AT 1792' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 448' WITH 40 SX CMT. 3RD PLUG AT 62' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5988	5993		
5975	5980		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
MAR 10 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

MAR 19 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3