

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-04482-00-00
Spot: NESWNW Sec/Twnshp/Rge: 10-19S-11W
1650 feet from N Section Line, 990 feet from W Section Line
Lease Name: MUSENBURG B Well #: 8
County: BARTON Total Vertical Depth: 3314 feet

Operator License No.: 3682
Op Name: CONNELL, MARK ALLEN
Address: 606 W ALBRO ST
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3151	1603	100 SX
SURF	8.625	323		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/18/2015 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MARK CONNELL Company: MARK CONNELL Phone: (620) 587-3595

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement and 400 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/18/2015 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded of perforations and topped with cement. Cut casing at 1603' and pulled casing to 1400'. Pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface with 90 sx cement. Pulled casing and hole stayed full.

GPS: 38.41535 -098.53267

Perfs:

Top	Bot	Thru	Comments
3081	3085		
2860	2866		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

MAR 25 2015 *CRM*

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

KCC WICHITA

MAR 18 2015

RECEIVED

Form CP-2/3

FEB 25 2015