

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-04477-00-00
Spot: NENWSW Sec/Twnshp/Rge: 10-19S-11W
2310 feet from S Section Line, 990 feet from W Section Line
Lease Name: MUSENBERG B Well #: D-2
County: BARTON Total Vertical Depth: 3381 feet

Operator License No.: 3682
Op Name: CONNELL, MARK ALLEN
Address: 606 W ALBRO ST
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3273	1525	100 SX
SURF	8.625	318		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/20/2015 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MARK CONNELL Company: MARK CONNELL Phone: (620) 587-3595

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/450 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/20/2015 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped off with cement. Cut casing at 1525'. Pulled casing to 1520' and pumped 175 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface with 110 sx cement and 50 # hulls. Pulled casing and hole stayed full.

GPS: 38.41175 -098.53235

Perfs:

Top	Bot	Thru	Comments
3226	3234		
3154	3160		
3136	3160		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: DP

MAR 25 2015 *exm*

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

KCC WICHITA

Form CP-2/3

FEB 25 2015

MAR 18 2015

RECEIVED