

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-20367-00-02  
Spot: S2S2SW Sec/Twnshp/Rge: 32-9S-23W  
330 feet from S Section Line, 1320 feet from W Section Line  
Lease Name: DAVIGNON Well #: 2-32  
County: GRAHAM Total Vertical Depth: 4040 feet

Operator License No.: 30717  
Op Name: DOWNING-NELSON OIL CO INC  
Address: PO BOX 1019  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4038		100 SX
SURF	8.625	176		135 SX

Well Type: SWD UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/05/2015 10:00 AM  
Plug Co. License No.: 31720 Plug Co. Name: STEWART WELL SERVICE INC  
Proposal Rcvd. from: BRIAN KARLIN Company: STEWART WELL SERVICE INC Phone: (785) 621-2610

Proposed Plugging Method: Ordered 150 sx 60/40 pozmix 4% gel cement w/300 # hulls.  
This well was plugged on 10/05/1994. Downing Nelson tried to wash well down. Drilled to 1240'. Hit iron in hole and stopped. Going to repug well from 1240' with all cement.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/05/2015 11:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran tubing to 1230' and pumped 120 sx cement. Good circulation of cement. Pulled tubing out and topped off with 20 sx cement full.

GPS: 39.21996 -099.91766


Remarks: QUALITY CEMENT

Plugged through: TBG

MAR 25 2015 *km*

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)  
KCC WICHITA

*CM*

MAR 09 2015

MAR 18 2015

RECEIVED

Form CP-2/3

cc: UIC