

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-011-24393-00-00
Spot: S2S2NWNE Sec/Twnshp/Rge: 20-25S-22E
1190 feet from N Section Line, 1980 feet from E Section Line
Lease Name: BLYTHE Well #: 5-6
County: BOURBON Total Vertical Depth: 882 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 1700 N WATERFRONT PKWY BLDG 600
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	842		117 SX
SURF	8.625	21		5 SX
T1	2.375	719		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/21/2015 12:00 AM
Plug Co. License No.: 31813 Plug Co. Name: BECKER, STEVE A. DBA A & A WELL SERVICE
Proposal Rcvd. from: CHRIS MOGOWN Company: _____ Phone: (620) 224-7406

Proposed Plugging Method: In accordance with the rules and regulations of the Kansas Corporation Commission.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 01/21/2015 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 2" tubing inside the 4.5" casing to 842'. Pumped and circulated 35 sacks of portland cement through the 2" casing at TD. Pulled 2" tubing up to 375'. Pumped and circulated cement through the 2" tubing from 375' to surface. Pulled remaining tubing and then topped off the well with cement. A total of 65 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
699	711		
680	689		

RECEIVED
KCC DIST # 3
MAR 17 2015
CHANUTE, KS

RD

Remarks:

Plugged through: TBG

MAR 25 2015
CKM

District: 03

Signed _____
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAR 19 2015

CONSERVATION DIVISION
WICHITA, KS