

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-011-24396-00-02
Spot: SENWNWSE Sec/Twnshp/Rge: 20-25S-22E
2240 feet from S Section Line, 2308 feet from E Section Line
Lease Name: BLYTHER Well #: 7-6
County: BOURBON Total Vertical Depth: 692 feet

Operator License No.: 9855
Op Name: GRAND MESA OPERATING COMPANY
Address: 1700 N WATERFRONT PKWY BLDG 600
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		500		
PROD	4.5	132		70 SX
SURF	8.625	21		5 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/19/2015 12:00 AM
Plug Co. License No.: 31813 Plug Co. Name: BECKER, STEVE A. DBA A & A WELL SERVICE
Proposal Revd. from: CHRIS MOGOWN Company: _____ Phone: (620) 224-7406

Proposed Plugging Method: In accordance with the rules and regulations of the Kansas Corporation Commission.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 01/19/2015 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 2" tubing inside the 4.5" casing to 500'. Pumped and circulated 10 sacks of portland cement through the 2" casing at TD. Pulled 2" tubing up to 160'. Pumped and circulated cement through the 2" tubing from 160' to surface. Pulled remaining tubing and then topped off the well with cement. A total of 17 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
673	688		
290	300		

RECEIVED
KCC DIST # 3
MAR 17 2015
CHANUTE, KS

RD

Remarks:

Plugged through: TBG

MAR 25 2015
OKM

District: 03

Signed _____
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAR 19 2015

CONSERVATION DIVISION
WICHITA, KS