

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-063-21926-00-00  
Spot: NENWSWSW Sec/Twnshp/Rge: 33-13S-31W  
1052 feet from S Section Line, 583 feet from W Section Line  
Lease Name: SPONEY Well #: 1-33  
County: GOVE Total Vertical Depth: 4680 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>9855</u>	<u>PROD</u>	<u>5.5</u>	<u>4671</u>		<u>175 SX</u>
Op Name: <u>GRAND MESA OPERATING COMPANY</u>	<u>SURF</u>	<u>8.625</u>	<u>222</u>		<u>165 SX</u>
Address: <u>1700 N WATERFRONT PKWY BLDG 600</u> <u>WICHITA, KS 67206</u>					

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/19/2015 12:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JOHN JOHNSON Company: SWIFT SERVICES, INC. Phone: (620) 617-3357

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls and 15 sx gel.  
Perforations: 4557' - 4561'. Port Collar at 2421' with 300 sx cement.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/19/2015 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing and pumped 50 sx cement w/150 # hulls, followed by 15 sx gel, followed by 280 sx cement. Checked backside and it was full.  
GPS: 38.87634 -100.77762

Perfs:

Top	Bot	Thru	Comments
4557	4561		

Remarks: SWIFT CEMENT TICKET # 27134


Plugged through: CSG

MAR 25 2015

CM

District: 04

Signed

  
(TECHNICIAN)

CM

FEB 23 2015