

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-20964-00-00
Spot: SENWNWSW Sec/Twnshp/Rge: 22-13S-32W
2065 feet from S Section Line, 573 feet from W Section Line
Lease Name: VAILE Well #: 1-22
County: LOGAN Total Vertical Depth: 4734 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>9855</u>	<u>PROD</u>	<u>5.5</u>	<u>4453</u>		<u>175 SX</u>
Op Name: <u>GRAND MESA OPERATING COMPANY</u>	<u>SURF</u>	<u>8.625</u>	<u>221</u>		<u>165 SX</u>
Address: <u>1700 N WATERFRONT PKWY BLDG 600</u> <u>WICHITA, KS 67206</u>	<u>T1</u>	<u>2.875</u>	<u>4412</u>		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/19/2015 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOHN JOHNSON Company: SWIFT SERVICES, INC. Phone: (620) 617-3357

Proposed Plugging Method: Ordered 365 sx 60/40 pozmix 4% gel cement, 400 # hulls and 12 sx gel.
Perforations: 4316' - 4321'. Port Collar at 2529' with 300 sx cement.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/19/2015 11:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:	Perfs:								
Tied on to casing and pumped 50 sx cement w/150 # hulls followed by 12 sx gel, followed by 265 sx cement w/150 # hulls. Casing full. Tied on to backside and squeezed with 15 sx cement. Shut in pressure 300 psi. GPS: 38.90755 -100.86917	<table border="1"><thead><tr><th>Top</th><th>Bot</th><th>Thru</th><th>Comments</th></tr></thead><tbody><tr><td>4316</td><td>4321</td><td></td><td></td></tr></tbody></table>	Top	Bot	Thru	Comments	4316	4321		
Top	Bot	Thru	Comments						
4316	4321								

Remarks: SWIFT CEMENT TICKET # 27133

Plugged through: CSG

MAR 25 2015 *CM*

District: 04 Signed *Marvin Mills* (TECHNICIAN) *CM*

FEB 23 2015

KCC WICHITA

Form CP-2/3

MAR 18 2015

RECEIVED