

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-109-21062-00-00  
Spot: SESENE SW Sec/Twnshp/Rge: 25-12S-32W  
1626 feet from S Section Line, 2582 feet from W Section Line  
Lease Name: A-K Well #: 1-25  
County: LOGAN Total Vertical Depth: 4740 feet

Operator License No.: 9855  
Op Name: GRAND MESA OPERATING COMPANY  
Address: 1700 N WATERFRONT PKWY BLDG 600  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4739		175 SX
SURF	8.625	221		165 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/18/2015 9:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JOHN JOHNSON Company: GRAND MESA OPERATING CO Phone: (620) 617-3357

Proposed Plugging Method: Ordered 360 sx 60/40 pozmix 4% gel cement, 15 sx gel and 300 # hulls.  
8 5/8" surface casing set at 221' w/165 sx cement. 5 1/2" production casing set at 4739' w/175 sx cement. DV Tool set at 2528' w/190 sx cement. TD 4740'. PBTd 4727'. Perforations: 4605' - 4609'. Well is non-commercial.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/18/2015 11:15 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Connected to 5 1/2" production casing and pumped 50 sx cement w/150 # hulls followed by 15 sx gel and 310 sx cement w/150 # hulls. Pressured to 400 psi. Connected to 8 5/8" surface casing and pumped 15 sx cement. Pressured up to 300 psi. Cement fell to 950'.  
02/19/2015- Topped off with 90 sx cement. Marvin Mills witnessed.  
GPS: 38.97938N -100.82358W

Perfs:

Top	Bot	Thru	Comments
4605	4609		

Remarks: SWIFT SERVICES TICKET # 27,131

Plugged through: CSG

MAR 25 2015 *cm*

District: 04

Signed Darrel Dipman  
(TECHNICIAN) *cm*

KCC WICHITA

MAR 18 2015

RECEIVED

FEB 25 2015