

15-175-00077-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR

Strike out upper line
when reporting plug-
ging of formations.

FORMATION PLUGGING RECORD

Seward County, Sec 18 Twp 35 Rge 32W (E) (W)
Location as "NE1/4NW1/4SW1/4" or footage from lines 1320' from North Line
Lease Owner J. M. Huber Corp. 1320' from West Line
Lease Name Cora Pound Well No. #1
Office Address Box 978 - Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-5-52 19
Application for plugging filed 12-6-52 19
Application for plugging approved 12-6-52 19
Plugging commenced 12-6-52 19
Plugging completed 12-6-52 19
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

NORTH

Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives - Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 6300' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				13 3/8	600'	None
				9 5/8"	2400'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled back with Rotary Mud to 400'; set plug and ran 25 sacks of cement through the drill pipe; mudded hole to 35', set plug and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1952
12-10-52
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to J. M. Huber Corporation
Address P. O. Box 978
Liberal, Kansas

STATE OF KANSAS, COUNTY OF SEWARD, ss.

I, W. W. Henson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. W. Henson
P. O. Box 978 - Liberal, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of December, 19 52

My commission expires September 10, 1955
Notary Public.

PLUGGING
FILE SEC 18 T 35 R 32
BOOK PAGE 63 LINE 73

FORMATION RECORD

<u>FORMATION</u>	<u>TOP</u>	<u>BOTTOM</u>
Surface Clay	0	146
Sand & Gravel	146	449
Gyp & Shale	449	585
Redbed & Gyp	585	607
Redbed & Shale	607	1628
Shale & Shells	1628	1948
Anhydrite & Shale	1948	2520
Dolomite	2520	2900
Lime, Shaly Lime	2900	3760
Shaly Sand	3760	3890
Limy Shale	3890	4380
Shaly Lime	4380	5550
Limy & Sand Shale	5550	6150
Lime	6150	6300
T.D.	6300	

I, R. E. McDaniel being first duly sworn on oath state that I have knowledge of the facts and matter herein set forth and that the same are true and correct.

R. E. McDaniel
Petroleum Engineer

Subscribed and sworn to before me this 22nd. day of December, 19 52.

J. Lewis E. J. J. J.
Notary Public

PLUGGING
FILE SEC. 18 T. 35 R. 322
BOX PAGE 3 LINE 43

Hutchinson County, Texas

STATE CORPORATION COMMISSION OF KANSAS
CONSERVATION DIVISION

Operator: J. M. Huber Corporation Address: Box 831, Borger, Texas

County: Seward TWP: 35S RGE: 32W Sed. No. 18

Lease Name: Corra Pound Well No. 1

Name of Field in which well is located: Wildcat

Drilling Commenced: October 19, 1952 Drilling Completed: December 3, 1952

Correspondence regarding this well should be sent to: Name: J. M. Huber Corporation

Address: Box 831, Borger, Texas


CASING:

13-3/8 600'

9-5/8 2400'

Production: Dry Hole

Is this an Oil well? _____, a Gas well? _____, or a Dry Hole? Dry Hole



STATE CORPORATION COMMISSION
CONSERVATION DIVISION
DEC 23 1952
Wichita, Kansas