

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD

Seward County, Sec. 15 Twp. 35S Rgo. 32 (E) (W) X

Location as "NE/CNWKSW" or footage from line: SW 1/4 NE 1/4

Lease Owner: Ted R. Lofland Estate

Lease Name: Light Well No. 1

Office Address: Box 1578 Liberal, Kansas 67901

Character of Well (completed as Oil, Gas or Dry Hole): Gas

Date well completed: 19__

Application for plugging filed: 3-23 1977

Application for plugging approved: 3-30 1977

Plugging commenced: 4-4 1977

Plugging completed: 4-7 1977

Reason for abandonment of well or producing formation: Chester Depleted

If a producing well is abandoned, date of last production: 10-75

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Clarence Thomas

Producing formation: Chester Depth to top: 6165 Bottom: TD Total Depth of Well: 6320

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8	524	none
				9 5/8	2310	None
				5 1/2	6312	2805

Describe in detail the manner in which the well was plugged, indicating where the mud ball was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet for each plug set.

Pump 2 sks. of hulls & 20 sks. of cement to 5800

Pump 35 sks. of cement from 2360 to 2260

Pump 75 sks. of cement from 500 to 400

Put 20 sks. of cement from 40 to 0

RECEIVED
STATE CORPORATION COMMISSION

AUG - 1 1979

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor: Sargents Casing Pulling Service Kansas No. 511
Address: Box 506 Liberal, Kansas 67901

STATE OF Kansas COUNTY OF Seward ss.

Ned E. Lowry (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Ned E. Lowry

Box 1578, Liberal, Kansas 67901

27th day of April 1977

Vernon T. Behrendt

My commission expires 12-31-79 Notary Public.

Please note that when this plugging report was filed it showed that this was a depleted Morrow well; however, it was Chester. Please correct your records.

Janice Heckman
Janice Heckman
7-30-79

