

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Seward SEC. 12 TWP. 35S RGE. 32 ~~EW~~
Location as in quarters or footage from lines:
C SW SE

		0	

Locate Well
correctly on above
Section Platt.

Lease Owner J. M. Huber Corporation (Operator #5703)
Lease Name Wallace "E" Well No. 1
Office Address 7120 I-40 West, Amarillo, TX 79106
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 11-9-82
Application for plugging filed 11-12-82
Plugging commenced 11-9-82
Plugging completed 11-9-82
Reason for abandonment of well or producing formation Commercial quantities of hydrocarbons not found
Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes (11-3-82)

Name of Conservation Agent who supervised plugging of this well Paul Luthe
Producing formation N/A Depth to top _____ bottom _____ T.D. 7600'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				10-3/4"	1596'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- Plug @ 4400-4353' w/50 sxs Class H
- Plug @ 1650-1550' w/70 sxs 50/50 Poz w/2% gel and 3% CaCl₂
- Plug @ 840-740' w/45 sxs 50/50 Poz w/2% gel and 3% CaCl₂
- Wooden BP @ 40' w/15 sxs 50/50 Poz w/2% gel and 3% CaCl₂
- Rat Hole 10 sxs 50/50 Poz w/2% gel and 3% CaCl₂
- Mouse Hole 10 sxs 50/50 Poz w/2% gel and 3% CaCl₂

Note: Water well released to surface owner.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sage Drilling

STATE OF TEXAS COUNTY OF POTTER, ss.
M. R. Griffin, District Prod. Mgr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. R. Griffin
7120 I-40 West, Amarillo, TX
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of November, 19 82



My Commission expires: 10/14/84

Eva M. Lile
Eva M. Lile
STATE CORPORATION COMMISSION

NOV 17 1982
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

WALLACE "E" NO. 1

CASING RECORD:	OPERATOR: J. M. Huber Corporation	DESCRIPTION:
10-3/4" set @ 1596'	CONTRACTOR: Sage Drilling Co., Inc.	C SW SE
w/1200 sax cement	COMMENCED: October 12, 1982	Section 12-35S-32W
TOTAL DEPTH:	COMPLETED: November 4, 1982	Seward County,
7600'		Kansas

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Red Bed	0	221	
Sand, Clay & Red Bed	221	950	
Red Bed & Sand	950	1500	
Red Bed & Anhydrite	1500	2450	
Anhydrite	2450	2830	
Lime & Shale	2830	3777	
Shale & Lime	3777	3915	
Lime & Shale	3915	4136	
Shale & Lime	4136	4197	
Lime & Shale	4197	4404	
Shale & Lime	4404	4515	
Lime & Shale	4515	4665	Ran DST #1
Lime	4665	4716	
Lime & Shale	4716	4839	
Shale & Lime	4839	5123	
Lime & Shale	5123	5230	
Shale & Lime	5230	5329	Ran DST #2
Lime & Shale	5329	5743	
Shale & Lime	5743	5820	
Lime & Shale	5820	6026	
Shale & Lime	6026	6054	
Lime & Shale	6054	6180	
Shale & Lime	6180	6246	
Lime & Shale	6246	6428	
Shale & Lime	6428	6510	
Lime & Shale	6510	6595	
Shale & Lime	6595	6670	
Lime & Shale	6670	7448	Ran DST #3
Shale & Lime	7448	7518	
Lime & Shale	7518	7600	Ran DST #4-8

I certify that this is a true and correct copy of the log on the above captioned well to the best of my knowledge.

SAGE DRILLING CO., INC.

BY John R. Bartholomew
John R. Bartholomew

Subscribed and sworn to before me this 1st day of December, 1982.

Louise K. Whitted
Louise K. Whitted, Notary Public

