


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Blitting Building
Wichita, Kansas

Seward County, Sec. 12 Twp. 35S Rge. 32 (E) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines G SE NW
Lease Owner J. M. Huber Corporation
Lease Name Wallace "B" Well No. 1
Office Address Box 831, Borger, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-23-52
Application for plugging filed 1-25-52
Application for plugging approved 1-22-52 (by phone)
Plugging commenced 1-22-52
Plugging completed 1-22-52
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 6373 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
None productive				13-3/8	600	0
				9-5/8	2100	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Pumped cement through drill pipe @ 300 feet 3/25 sacks. Fifteen sacks at top of surface casing. Hole was filled with 9.5#/gal mud, visc. 55 sec., before spotting cement. Well was cemented by Halliburton Cementing Co.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lease Owner - Company tools
Address _____

STATE OF Texas, COUNTY OF Hutchinson, ss.
G. Bullitt Williams (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bullitt Williams

Box 831, Borger, Texas
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of January, 1952.

My commission expires June 1, 1953
Virginia Anderson
Hutchinson County, Texas Notary Public.

23-8390-3 6-51-20M
PLUGGING
FILE SEC - T 35 (B3.2W)
DATE 1-22-52

RECEIVED
STATE CORPORATION COMMISSION
FEB 1 X 1952
CONSERVATION DIVISION

cc: Phillips Petroleum Company, Land and Geological Dept., Bartlesville, Oklahoma
Attn: Mr. E. L. Kistler

cc: Stanolind Oil and Gas Company, First Nat'l Bank Bldg., Wichita, Kans.
Attn: Mr. G. C. Mahaffy, Land Dept.

cc: Wood River Oil & Refg. Co., Inc., 320 W. Douglas, Wichita, Kansas
Attn: Mr. C. C. Chapin

cc: Mr. Ted R. Lofland, 109 E. Third, Liberal, Kansas

cc: H. L. Hunt, Hunt Oil Co., Mercantile Bank Bldg, Dallas, Texas

2 cc: Kansas Corp. Com.

1971

D R I L L E R ' S L O G

COMPANY: J. M. HUBER CORPORATION
 CONTRACTOR: J. M. HUBER CORPORATION

LOCATION: C SE NW 12-35S-32W,
 Seward County, Kansas

FARM NAME: WALLACE "B" #1

ELEVATION: 2741

COMMENCED: DEC. 13, 1951

PRODUCTION: D & A

COMPLETED: JAN. 23, 1952

CASING: 13-3/8" @ 600'

9-5/8" @ 2400'

Clay & sd	130	Lime, sh	5050
Shells, sh str	570	Lime	5666
Red bed, sh	600	Lime, sh	5749
Red bed	950	Lime	5833
RB, shells	1535	Im, sh	5896
RB, salt, shells	1588	Shale	5999
RB, shells	2030	Lime, sh	6025
Sh, lime, anhy	2373	Shale	6050
Lime	2400	Im, sh	6101
Im, sh	2475	Shale	6118
Lime	2666	Im, sh	6153
Lime, sh	2800	Sh	6187
Lime	3335	Im, sh	6217
Im, sh	3860	Im	6230
Im, sh, sd	3966	Im, sh	6254
Im, sh	4343	Im	6261
Shale	4417	Im, sh	6373
Im, sh	4735		
Lime	4800		
Lime, sh	4955		
Lime	5012		

STATE OF TEXAS
 COUNTY OF HUTCHINSON

I, G. Bullitt Williams, hereby certify that the above is a true and correct copy of the log of the #1 Wallace B, located in the C of the Southeast, Northwest, Section 12-35S-32W, Seward County, Kansas.

G. Bullitt Williams

G. Bullitt Williams
 Petroleum Engineer
 J. M. HUBER CORPORATION

Sworn and subscribed to before me, a Notary Public, this the 28th day of January, 1952.

Virginia Anderson

Notary Public,
 Hutchinson County, Texas

- cc: State of Kansas, State Corporation Commission, Conservation Division, 800 Bitting Building, Wichita, Kansas
- cc: Phillips Petroleum Company, Land and Geological Dept., Bartlesville, Okla., Attn: Mr. E. L. Kistler
- cc: Stanolind Oil and Gas Co., First Nat'l Bank Bldg., Wichita, Kansas Attn: Mr. Geo C. Mahaffy, Land Dept.
- cc: Wood River Oil & Refg. Co., Inc., 321 W. Douglas, Wichita, Kansas, Attn: Mr. C. C. Chapin
- cc: Mr. Ted R. Lofland, 109 E. 3rd, Liberal, Kansas
- cc: Mr. H. L. Hunt, Hunt Oil Company, Mercantile Bldg., Dallas, Texas

PLUGGING

FILE NO. 12-35S-32W

DATE 1/29/52

FEB 1 X 1952

CONSERVATION DIVISION
 WICHITA, KANSAS