

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Light Unit
 WELL NUMBER B-1
660 Ft. from S Section Line
4620 Ft. from E Section Line
 SEC. 9 TWP. 35 RGE. 32 (E) or (W)
 COUNTY Seward
 Date Well Completed 1/6/60
 Plugging Commenced 10-23-98
 Plugging Completed 11-2-98

LEASE OPERATOR HI Inc.
 ADDRESS 110 W. 3rd Liberal Ks. 67901
 PHONE (316) 624-8484 OPERATORS LICENSE NO. 7123
 Character of Well Gas
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)
 by Gary Winters (KCC District Agent's Name).
 Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Cherokee Depth to Top 5539 Bottom 5545 T.D. 6275
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				5 1/2	6270	2825'
				8 5/8	2478'	635'
				13 3/8	489'	-0-

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plug #1 25 SKS cnt, 100# hulls 4574'-4374' displ. w/9# mud. #2 50 SKS cnt, 635-598' circulating plug method displ. w/9# mud. #3 70 SKS cnt, 500'-300' circ. method displ. w/9# mud. #4 20 SKS cnt, 40'-0'.


(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547
 Address P.O. Box 506 Liberal Ks. 67905-0506
 NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: H.I., Inc.
 STATE OF Kansas COUNTY OF Seward, ss.

Harold E. Box (Employee of Operator) or (Operator) of
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
 statements, and matters herein contained and the log of the above-described well as filed that
 the same are true and correct, so help me God.

(Signature) Harold E. Box
 (Address) P.O. Box 2526, Liberal, KS. 67801

SUBSCRIBED AND SWORN TO before me this 11th day of December, 19 98



Carolyn K. Buck
 Notary Public