

15-175-20817-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Seward SEC. 3 TWP. 35S RGE. 32 E/W  
Location as in quarters or footage from lines:  
Approximately C E/2 (2660' FNL & 1550' FEL)


Lease Owner J. M. Huber Corporation  
Lease Name Light "J" Well No. 1  
Office Address 7120 I-40 West, Amarillo, Texas 79106  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed 12-25-84  
Application for plugging filed 1-10-85 (Verbal from Paul Luthe  
Plugging commenced 12-25-84 (3:30 p.m.) 12-25-84)  
Plugging completed 12-26-84  
Reason for abandonment of well or producing formation Dry Hole

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes (CC)

Name of Conservation Agent who supervised plugging of this well Paul Luthe  
Producing formation N/A Depth to top \_\_\_\_\_ bottom T.D. 6300'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	1505'	None

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

TIH w/DP open-ended and set plugs as follows:  
Plug #1: 50 sx 1550-1450'  
Plug #2: 50 sx 760-660'  
Plug #3: 10 sx w/rubber plug & CS hulls 40-0'

All cement: 60-40 Poz w/2% gel & 3% CaCl

RECEIVED  
STATE CORPORATION COMMISSION

JAN 14 1985

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Johnson Drilling Company, Inc. (Drilling Contractor)  
BJ Hughes (Cementer)

STATE OF Texas COUNTY OF Potter, ss.  
William D. Siddens (employee of owner) or ~~(owner or operator)~~ of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) William D. Siddens  
7120 I-40 West, Amarillo, TX 79106  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of January, 19 85

Kary Cahes  
Notary Public.

My Commission expires: 2-15-85

