

15-175-10180-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Seward County. Sec. 2 Twp. 35 Rge. 32 (W)

Location as "NE/CNW/SW" or footage from lines C NE/4 SW/4  
Lease Owner J. M. Huber Corp.  
Lease Name Light Estate "C" Well No. 2  
Office Address Box 978, Liberal, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 2-28-55 19  
Application for plugging filed 2-27-55 19  
Application for plugging approved 2-27-55 19  
Plugging commenced 2-28-55 19  
Plugging completed 2-28-55 19  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 6260 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1600'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Spotted 45 sacks pozmix at 6010'; filled hole w/mud to 557'; placed 1 sack of hulls w/plug and spotted 25 sacks pozmix. Filled w/mud to 10'. Capped w/1 sack hulls, set plug and spotted 5 sacks pozmix.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 4 1955  
1-4-55  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor J. M. Huber Corp.  
Address Box 978, Liberal, Kansas

STATE OF KANSAS, COUNTY OF SEWARD, ss.  
R. E. McDaniel (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R E McDaniel  
Box 978, Liberal, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of March, 19 55

My commission expires July 27, 1957  
Notary Public.

PLUGGING  
FILE SEC. 2 T 35 R 32 W  
BOOK PAGE 100 LINE 41


WELL RECORDWell Name: Light Estate C #2Well Location: Cen. NE/4 SW/4 Section 2, Township 35, Range 32W,  
Seward County, Kansas.Well Owner: J. M. Huber Corp.Drilling Commenced: 2-5-55Drilling Completed: 2-27-55Well Completed: 2-28-55Total Depth: 6260'

<u>Formation</u>	<u>Depth</u>
Clay and sand	0- 76
Sand & shells	76- 291
Gyp, sand & clay	291- 540
Shells & redbed	540-1020
Redbed & shale	1020-1443
Redbed & shells	1443-1547
Shale & shells	1547-1708
Redbed & shale	1708-1888
Shale	1888-2172
Redbed & shell-shale	2172-2200
Shale & lime	2200-3059
Lime	3059-3147
Lime & shale	3147-4122
Shale	4122-4223
Lime & shale	4223-4525
Lime	4525-4725
Lime & chert	4725-4857
Lime	4857-4907
Lime & chert	4907-5124
Lime	5124-5172
Lime & chert	5172-5224
Lime	5224-5318
Lime & chert	5318-5357
Lime	5357-5387
Lime & shale	5387-5418
Lime & chert	5418-5464
Lime	5464-5515
Lime & shale	5515-5545
Lime	5545-5607
Lime & shale	5607-6260
Total Depth	6260

- Page 1 -

**RECEIVED**  
STATE CORPORATION COMMISSION

MAR 4 X 1955

CONSERVATION DIVISION  
White, Kansas

WELL RECORD (Light Estate C #2)

STATE OF KANSAS, COUNTY OF SEWARD, SS:

R. E. McDaniel, employee of owner of the above named well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

R E McDaniel

Subscribed and sworn to before me this 3 day of March, 1955.

My commission expires:

7-27-57

**RECEIVED**  
STATE CORPORATION COMMISSION  
MAR 4 1955  
CONSERVATION DIVISION  
Wichita, Kansas