

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

		X	

Locate well correctly on above Section Plat

Seward County, Sec. 2 Twp. 35S Rge. 32W (E) (W)
Location as "NE/CNWSW" or footage from lines. C NW NE
Lease Owner J. M. Huber Corporation
Lease Name Neff Well No. 2
Office Address P. O. Box 911, Amarillo, Texas 79105
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed March 2 1955
Application for plugging filed July 7 1970
Application for plugging approved July 9 1970
Plugging commenced August 28 1970
Plugging completed August 29 1970
Reason for abandonment of well or producing formation uneconomical
If a producing well is abandoned, date of last production August 15 1970
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. E. Eves
Producing formation Morrow Depth to top 5935 Bottom 5985 Total Depth of Well 6147 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow	Lime	5935	5985	13-3/8"	400'	-0-
				9-5/8"	2400'	-0-
				7"	6145'	2635'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spotted 60 sacks cement from 6100'-5848'; filled with mud laden fluid to 900'.
Spotted 50 sacks cement from 900'-800'; filled with mud laden fluid to 50'.
Spotted 15 sacks cement from 50'-5'. Cut off surface casing, welded on plate.
Well P&A.

RECEIVED
STATE CORPORATION COMMISSION
SEP 3 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Daco Well Service Company
Address 1700 S. Main, Borger, Texas 79007

STATE OF Texas, COUNTY OF Potter, ss.
Bob Conley (employee of owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bob Conley
P.O. Box 911, Amarillo, Texas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of September, 1970

My commission expires June 1, 1971
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
JUL 9 1970
CONSERVATION DIVISION
Wichita, Kansas

Neff #2
Section 2-T35S-R32W
Seward County, Kansas

Driller's Log

<u>Depth</u>	<u>Formation</u>
0'-400'	Sand, Clay
400'-2191'	Red Bed, Shales
2191'-4015'	Lime, Shale
4015'-4251'	Shale
4251'-4626'	Lime, Shale
4626'-4711'	Lime, Chert
4711'-4819'	Lime, Shale
4819'-5241'	Lime, Chert
5241'-5410'	Lime
5410'-5693'	Lime, Chert
5693'-6108' (TD)	Lime, Shale

Certificate:


I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.


Bob Conley

Title: District Production Clerk

Subscribed and sworn to before me, a Notary Public,

this 7th day of July 1970.


Notary Public