


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Seward County, Sec. 14 Twp. 35S Rge. (E) 33 (W)
Location as "NE/CNW/SW" or footage from lines 1700' FNL & 660' FWL
Lease Owner Amoco Production Company
Lease Name Matkin "A" Well No. 1
Office Address Security Life Bldg., Denver, Colo.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 26, 19 74
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced June 26, 19 74
Plugging completed June 26, 19 74
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Edgar Eves of Sublette)

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 6250 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|-------|--------|--------|------------|
| | Surface | 0 | 1540' | 8-5/8" | 1540' | None |
| | Casing | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 1000 Feet,
35 sax Cement Plug @ 1000 Feet; Heavy Mud
to 40 Feet; Plug & Bridge & 15 sax Cement
to Base of Cellar; 2 sax Cement in Rat Hole.
Job Completed @ 4 A.M.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
Address Box 112, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEDGWICK
John R. Bartholomew of Sage Drilling Co. (employee or owner or power of attorney or operator) of the above described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John R. Bartholomew
500 Bitting Bldg., Wichita, Kansas
(Address)



Subscribed and Sworn to before me this 1st day of July, 19 74.
November 26, 1974
Louise K. Whitted - Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
JUL 3 1974
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOGMATKIN "A" NO. 1

| | | |
|------------------------------------|--------------------------------|--|
| CASING RECORD: | OPERATOR: Amoco Production Co. | DESCRIPTION: |
| 8-5/8" @ 1540' w/950 sax Cement | CONTRACTOR: Sage Drilling Co. | 1700' FNL and 660' FWL of |
| TOTAL DEPTH: 6250' | COMMENCED: June 6, 1974 | Sec. 14-35S-33W Seward County, Kansas. |
| | COMPLETED: June 26, 1974 | |

| <u>FORMATION</u> | <u>FROM</u> | <u>TO</u> | <u>REMARKS</u> |
|-------------------|-------------|-----------|----------------|
| Surface Soil | 0 | 40 | |
| Sand | 40 | 931 | |
| Red Bed & Sand | 931 | 1300 | |
| Shale | 1300 | 2094 | |
| Shale & Anhydrite | 2094 | 2322 | |
| Shale & Lime | 2322 | 2916 | |
| Lime & Shale | 2916 | 6250 | D&A |

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By John R. Bartholomew
John R. Bartholomew



Subscribed and sworn to before me this 1st day of July, 1974.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974.

RECEIVED
STATE CORPORATION COMMISSION
JUL 3 1974
CONSERVATION DIVISION
Wichita, Kansas