

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-10239-00-01
Spot: SWNENW Sec/Twnshp/Rge: 12-35S-30W
990 feet from N Section Line, 1650 feet from W Section Line
Lease/Unit Name: ADAMS RANCH Well Number: 1-12
County: MEADE Total Vertical Depth: 6540 feet

Operator License No.: 6567
Op Name: KAISER-FRANCIS OIL CO.
Address: PO BOX 535528
TULSA, OK 74153

Production Casing Size: 5.5 feet: 6314 WITH 100 SX CMT
Surface Casing Size: 9.625 feet: 1401 WITH 500 SX CMT

#212 55

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/03/2003 12:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: BUD AYLETT Company: KAISER FRANCIS Phone: (405) 232-8624

Proposed Plugging Method: PUMP 25 SX CMT & 100# HULLS. PLUG AT 1430' WITH 60 SX CMT. PLUG AT 690' WITH 45 SX CMT. PLUG AT 0-40' WITH 15 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/03/2003 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 5990'. PERFS AT 5168-72'. CIBP @ 6000' WITH 10 SX CMT ON TOP. PUMP 100# HULLS WITH 25 SX CMT. DISPLACE WITH MUD. PRESSURE CASING TO 500 PSIG & SHUT IN. 1ST PLUG PULL OUT OF HOLE TO 1430'. CIRCULATE HOLE WITH MUD & PUMP 60 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 690'. CIRCULATE HOLE & PUMP 45 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 15 SX CMT TO SURFACE.

RECEIVED
OCT 14 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD. RECOVERED 2500' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
OCT - 9 2003
KCC Dodge City

Signed

Jim Holland
(TECHNICIAN)

INVOICED
DATE 10-14-03
REV. NO. 2004060621

SA