

1 050830

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,048 - 0000
C NE SW, SEC. 11, T 35 S, R 30 (W/E)
1980 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8685

Lease Name Adams Ranch Well # 5 SWD

Operator: William Gruenerwald & Assoc., Inc.
Name & Address P.O. Box 909
Colorado Springs, CO 80901

County Meade 205.89

Well Total Depth 6335 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1460

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, Ks 67901

Company to plug at: Hour: 10:00 pm Day: 9 Month: July Year: 1986

Plugging proposal received from Doug Blain

(company name) _____ (phone) _____

were: 5 1/2" at 6335 PBTD 6300' Perfs at 6098-6118'

1st plug pump 2 sacks hulls and 40 sx cement to bottom

2nd plug loaded hole with heavy mud, pulled casing to 1490' and pumped 50 sx cement

3rd plug pulled casing to 750' and pumped 40 sx cement

4th plug pumped 10 sx cement from 40' to surface

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:00 am Day: 10 Month: July Year: 1986

ACTUAL PLUGGING REPORT 1st plug 2 sacks hulls and 40 sx cement to bottom,

2nd plug spotted 50 sx cement at 1490' through 5 1/2", 3rd plug spotted 40 sx at 750'

through 5 1/2", 4th plug spotted 10 sx cement at 40' filling the hole to 0"

Remarks: Recovered 1732' of 5 1/2" production casing. Used common cement. (Sargent's)
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-15-86

INV. NO. 14382

7-10

STATE CORPORATION COMMISSION

JUL 14 1986

CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Lacey
(TECHNICIAN)

FORM CP-2/3
Rev. 01-84