

To: 1.090898
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

2-10

API NUMBER 13-119-20,989-0000
S/2 NE NE, SEC. 4, T 35 S, R 30 W EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5225

Operator: Quinque Operating Company
Name & Address P.O. Box 2738
Liberal, KS 67905-2738

990 feet from NE section line
660 feet from E section line

Lease Name Adams Well # KC 1-4
County Meade 212.88

Well Total Depth 6550 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1465

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor BEREDCO, Inc. License Number 5147
Address 401 E. Douglas, Ste. 402, Wichita, KS 67202

Company to plug at: Hour: 3 a.m. Day: 10 Month: 2 Year: 1998

Plugging proposal received from Kent Johnson
(company name) BEREDCO, Inc. (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1490' with 50 sx cement, 2nd plug at 550' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5 a.m. Day: 10 Month: 2 Year: 1998

ACTUAL PLUGGING REPORT 1st plug at 1490' with 50 sx cement,

2nd plug at 550' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED

FEB 13 1998
2-13-98

CONSTRUCTION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

~~XXXX~~ did not observe this plugging.

INVOICED

DATE FEB 18 1998

INV. NO. 50101
2-10

Signed _____
(TECHNICIAN)

EFFECTIVE DATE: 12-16-97

DISTRICT #
19A7, Yes, No

State of Kansas

NOTICE OF INTENTION TO DRILL

119-20,989-0000

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 12 20 97
month day year

Spot S/2 NE/4 NE/4 Sec 4 Twp 35 S, Rg 30 Eas X Use

OPERATOR: License # 5225
Name: Quingue Operating Company
Address: P.O. Box 2738
City/State/Zip: Liberal, KS 67905
Contact Person: Michael Moore
Phone: (316) 624-2578

990 feet from South North line of Section
660 feet from East West line of Section
IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side
County: Meade
Lease Name: Adams Well #: KC 1-4
Field Name: Adams Ranch

CONTRACTOR: License #: 5147
Name: Beradco, Inc.

Is this a Predrilled/Spaced Field? yes X no
Target Formation(s): St. Louis

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield X Mud Rotary
... Gas ... Storage X Pool Ext. ... Air Rotary
... OUVG ... Disposal ... Wildcat ... Cable
... Seismic: ... # of Holes ... Other
... Other

Nearest lease or unit boundary: 320'
Ground Surface Elevation: 2530' feet MSL
Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no

If OUVG: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Depth to bottom of fresh water: 440'
Depth to bottom of usable water: 500' (FORMAN)
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 1500'
Length of Conductor pipe required: 40' (NONE)
Projected Total Depth: 6600'
Formation at Total Depth: St. Louis

Directional, Deviated or Horizontal wellbore? yes X no

Water Source for Drilling Operations:
X well ... farm pond ... other

If yes, true vertical depth:

Permit #: APPL. FOR FROM AWR
Will Cores Be Taken? yes X no

Bottom Hole Location:

If yes, proposed zone:

Exp. 6/11/98

520' Alt. I Req.

AFFIDAVIT

The undersigned hereby affirms that the information furnished herein is true and correct to the best of my knowledge and belief.

Pusher Kent Beradco
SPUD DATE 1-28-98 INIT. SP
LENGTH SURFACE PLANNED 1450' by 8 3/8"
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 3/8" @ 1-465 CONDUCTOR
ANHYDRITE T- B- ELEVATION
TD 6550 FORMATION
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ Ft. W/ SX
1/2 Base Anyh. @ 550 Ft. W/ 40 SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 1490 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL 1 SX (Irr. Well / Pond
Hauling
TECHNICIAN 5M DATE 2-6-98
TYPE OF CEMENT 60/40 67%
STARTING TIME 3:00 (AM/PM) DATE 2-10-98
COMPLETION TIME 5:00 (AM/PM) DATE 2-10-98
CEMENT COMPANY Habluer