

12-29-15-119-10249-2090

1 020277

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 10/18/69

E/2 SW SE, SEC. 3, T 35 S, R 30 W/E

660 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8685

Lease Name W. Fox Well # 1

Operator: William Gruenerwald & Associates, Inc
Name & Address: P.O. Box 909 60669
Colorado Springs, CO 80901 80960

County Meade 205.30
Well Total Depth 6317 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1390

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 2:30 p.m. Day: 28 Month: 12 Year: 19 89

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 5 1/2" at 6317' PBTD 6260' Perfs at 6244-49'

- 1st plug pump 1 sx hulls and 25 sx cement at perfs, load hole with mud,
- 2nd plug pump 50 sx cement at 1400',
- 3rd plug pump 40 sx cement at 700',
- 4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4 p.m. Day: 29 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement at perfs,
loaded hole with mud,
2nd plug pumped 50 sx cement at 1400',
3rd plug pumped 40 sx cement at 700',
4th plug pumped 10 sx cement at 40'.

Displaced all plugs with mud.

Remarks: Used common cement by Sargent's Casing Pulling. Recovered 2605' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
1-4-90

DATE 1-12-90

Signed Glenn R. Barlow (TECHNICIAN)

INV. NO. 27015
12-29 FEB 28 1990