

1 040200

11-23

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 175-21,056 - 0000  
NW NE, SEC. 1, T 35 S, R 32 W/E  
4620 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Kivett "A" Well #1

Operator: Berexco Inc.

County Seward 213.27

Name & Address 970 Fourth Financial Center  
Wichita, KS 67202

Well Total Depth 6562 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1623

Abandoned Oil Well Gas Well Input Well SWD Well O&A x

Other well as hereinafter indicated

Plugging Contractor Beredco, Inc. License Number 5147

Address 401 East Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 8 a.m. Day: 23 Month: 11 Year: 19 88

Plugging proposal received from Gary Marshall

(company name) Beredco, Inc. (phone) 316-265-3511

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1550-1600' Elevation 2751 KB

1st plug at Chase Group with 100 sx cement. 2nd plug at 1600' with 50 sx cement,

3rd plug at 800' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:15 p.m. Day: 23 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 2800' with 100 sx cement,

2nd plug at 1600' with 50 sx cement,

3rd plug at 800' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

did not observe this plugging.

DATE 12-12-88

INV. NO. 23306

11-23

JAN 06 1989

FEB 10 1989

RECEIVED STATE CORPORATION COMMISSION

DEC 9 1988 12-9-88

CONSERVATION DIVISION Wichita, Kansas

Signed Stephen J. Pfeifer (TECHNICIAN)