

11-20

To: 1 080010
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-21,109 - 0000

SW NE NW, SEC. 15, T 35 S, R 31 W/EX
990 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9262

Lease Name Ross Well # 6-1

Operator: Lowry Exploration, Inc.

County Seward 182.65

Name & Address P.O. Drawer 1847

Well Total Depth 5620 feet

Liberal, KS 67905-1847

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1587

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Zenith Drilling Corporation License Number 5141

Address 505 4th Financial Center, Wichita, KS 67202

Company to plug at: Hour: 3:30 p.m. Day: 20 Month: 11 Year: 1989

Plugging proposal received from Ned Lowry

(company name) Lowry Exploration, Inc. (phone) 316-624-8141

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1650'

1st plug at 3060' with 100 sx cement, 2nd plug at 1650' with 50 sx cement,

3rd plug at 800' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Mike Spain (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:30 p.m. Day: 20 Month: 11 Year: 1989

ACTUAL PLUGGING REPORT 1st plug at 3060' with 100 sx cement,

2nd plug at 1650' with 50 sx cement,

3rd plug at 800' with 40 sx cement,

4th plug at 40-0' with 15 sx cement,

5th plug to circulate rathole with 10 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
NOV 19 1989
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 1-3-1990

INV. NO. 26864

Signed Mike Spain (TECHNICIAN)

15-175-21109-0000

FORM MUST BE TYPED
FORM C-1 12/88

State of Kansas EFFECTIVE DATE: 10-31-89 FORM MUST BE SIGNED
NOTICE OF INTENTION TO DRILL 175-21,109 ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date November 1 1989
month day year

SW NE NW Sec 15 Twp 35 S Rg 31 East West

OPERATOR: License # 09262
Name: Lowry Exploration, Inc.
Address: P. O. Drawer 1847
City/State/Zip: Liberal, KS 67905-1847
Contact Person: Ned Lowry
Phone: (316) 624-8141

990 feet from South line of Section
3630 feet from East line of Section
(Notes: Locate well on Section Plat Below)

CONTRACTOR: License #: Zenith Rig
Name: undetermined

County: Seward
Lease Name: Ross Well #: 6-1
Field Name: N/A

Well Drilled For: Well Class: Type Equipment:
X Oil ... Inj ... Infield .X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... DWD ... Disposal .X Wildcat ... Cable
... Seismic; ... # of Holes

Is this a Prorated Field? ... yes .X no
Target Formation(s): Marmaton
Nearest lease or unit boundary: 990 ft.
Ground Surface Elevation: 2689 feet MSL

If DWD: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Domestic well within 330 feet: ... yes .X no
Municipal well within one mile: ... yes .X no
Depth to bottom of fresh water: 550
Depth to bottom of usable water: 550

Directional, Deviated or Horizontal wellbore? ... yes .X no
If yes, total depth location:

Surface Pipe by Alternate: .X 1 ... 2
Length of Surface Pipe Planned to be set: 1600
Length of Conductor pipe required: 40
Projected Total Depth: 5700
Formation at Total Depth: Marmaton

Exp. 4/26/90


Water Source for Drilling Operations:
X well ... farm pond ... other
DWR Permit #: Existing water well in SE-SE Sec 1
Will Cores Be Taken?: ... yes .X no
If yes, proposed zone:

550' Alt. I Req.

AFFIDAVIT

PUSHER TO 5620 FORMATION Marmaton
SURFACE PIPE 8 7/8 @ 1587
ANHYDRITE 1650 ELEVATION
STARTING TIME & DATE 3:30 PM
COMPLETION TIME & DATE 9:30 PM
1st PLUG @ 3060 FT. W/ 100 SX
2nd PLUG @ 1650 FT. W/ 50 SX
3rd PLUG @ 800 FT. W/ 40 SX
4th PLUG @ 400 FT. W/ 15 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 10 SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY B.J.
TECHNICIAN M.S.
TYPE OF CEMENT 60/40 6/8

Spud 11-11-89



Kansas
Oklahoma

Spud date: Agent: CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE COMMISSION
OCT 10 1989
CONSERVATION DIVISION
Wichita, Kansas

- REMEMBER TO:
- File Drill Pit Application (form COP-1) with Intent to Drill;
- File Completion Form ACO-1 within 120 days of spud date;
- File acreage attribution plat according to field prorator orders;
- Notify appropriate district office 48 hours prior to workover or re-entry;
- Submit plugging report (CP-4) after plugging is completed;
- Obtain written approval before disposing or injecting salt water.