

12-30-87

To: 1 070494
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,993-0000
C W/2 W/2 , SEC. 13 , T 35 S, R 31 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 8060

Operator: Zinke & Trumbo, Ltd.

Name & Address P.O. Box 1816

Liberal, KS 67905-1816

1101 feet from S section line

4620 feet from E section line

Lease Name Nancy Louderback Well # 1-13

County Seward 214.50

Well Total Depth 6600 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1500

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Slawson Drilling License Number 5657

Address 200 Douglas Bldg., 104 South Broadway, Wichita, KS 67202

Company to plug at: Hour: 1 a.m. Day: 30 Month: 12 Year: 19 87

Plugging proposal received from Keith Hill

(company name) Zinke & Trumbo, Ltd. (phone) 316-624-0156

Elevation 2669'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1500-1600'

1st plug at 1550' with 50 sx cement, 2nd plug at 500' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3 a.m. Day: 30 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1550' with 50 sx cement,

2nd plug at 500' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

STATE CORPORATION COMMISSION

JAN 04 1988

1-4-88

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging.

DATE 1-11-88

INV. NO. 19521

12-30

Signed Dan Goodrow (TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... 12 month 15 day 87 year

API Number 15- 175-20,993-0000 Irregular Section N-S East
C. W/2 W/2 Sec...13 Twp.35.. S, Rg.31... X West
1101 Ft. from South Line of Section
4620 Ft. from East Line of Section

OPERATOR: License # 08060
Name Zinke & Trumbo, Ltd.
Address P.O. Box 1816
City/State/Zip Liberal, KS 67905-1816
Contact Person Keith Hill
Phone (316) 624-0156

Nearest lease or unit boundary line 660 feet
County Seward
Lease Name NANCY LOUDERBACK Well # 1-13

CONTRACTOR: License # 5657
Name Slawson Drilling
City/State Wichita, KS

Ground surface elevation 2669 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

Well Drilled For: Well Class: Type Equipment:
X Oil Storage Infield X Mud Rotary
X Gas Inj X Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Depth to bottom of fresh water 500+
Depth to bottom of usable water 600
Surface pipe by Alternate 1-2 X

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Surface pipe planned to be set 1500'
Conductor pipe required 80'
Projected Total Depth 6600 feet
Formation Chester

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 12-9-87 Signature of Operator or Agent Jan Schartz Title Agent WW

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 620 feet per Alt. 1A
This Authorization Expires 6-8-88 Approved By PCH 12-8-87 12-11-87 RL

* WAS: C-SW-NW 17W FSL
Set 1500' of 8 5/8" on 12-19-87
51 of 20"

C. W/2 W/2 Sec...13 Twp..35..S, Rg..31... X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug depth (ft.), Formation, and Class. H.
1st plug @ ft. deep... 1530' or formation with... 50 SX... feet of... Class H
2nd plug @ ft. deep... 750' or formation with... 40 SX... feet of... Class H
3rd plug @ ft. deep... 40' or formation with... 10 SX... feet of... Class H
4th plug @ ft. deep... or formation with... feet of...
5th plug @ ft. deep... or formation with... feet of...

(2) Rathole to surface minus 5 feet 10 SX (b) Mousehole to surface minus 5 feet 10 SX

Jack Richardson
PUSHER Keith Hill w/ ZAT
TD 6600' FORMATION Chester
SURFACE PIPE 8 5/8" @ 1500'
ANEHYDRITE 1500' @ ELEVATION 2669'
STARTING TIME & DATE 1:00a 12-30-87
COMPLETION TIME & DATE 3:00a 12-30-87
1st PLUG @ 1550 FT. W/ 50 SX
2nd PLUG @ 500 FT. W/ 40 SX
3rd PLUG @ 40 FT. W/ 10 SX
4th PLUG @ FT. W/ SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ To Landowner SX
CEMENT COMPANY Hillborton Allied
TECHNICIAN D.G. 6/40 670

RECEIVED
STATE COMMISSION OF COMMISSIONERS
JAN 04 1988
CONSERVATION DIVISION
Wichita, Kansas