

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21795-00-00
Spot: NE Sec/Twnshp/Rge: 12-35S-31W
1320 feet from N Section Line, 2100 feet from E Section Line
Lease/Unit Name: R E ADAMS Well Number: 1-12
County: SEWARD Total Vertical Depth: 6521 feet

Operator License No.: 30604
Op Name: RAYDON EXPLORATION, INC.
Address: 9400 N. BROADWAY #400
OKLAHOMA CITY, OK 73114

Conductor Pipe: Size 13.375 feet: 130
Surface Casing: Size 8.625 feet: 1675 WITH 700 SX CMT
Production: Size 4.5 feet: 3111 WITH 190 SX CMT
Liner: Size feet: \$211.93

Well Type: GAS UIC Docket No: Date/Time to Plug: 08/30/2001 9:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: BOTTOM PLUG PUMP 100# HULLS & 20 SX CMT. 1ST PLUG AT 1700' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/30/2001 1:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


PBTD 3037'. PERFS AT 2790 - 2794'. 1ST PLUG PUMP 20 SX CMT & 100# HULLS OVER PERFS. LOAD HOLE WITH MUD. 2ND PLUG PULL TO 1700' & SPOT 50 SX CMT. 3RD PLUG PULL TO 600' & SPOT 40 SX CMT. 4TH PLUG PULL TO 40' & CIRCULATE 10 SX CMT TO SURFACE.

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2245' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED

SEP 06 2001

KCC WICHITA

INVOICED

AUG 31 2001

DATE 9-6-01

INV. NO. 2002060359



Form CR-23

