

1 060590

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C E/2 SE SE, SEC. 10, T 35 S, R 31 W/X
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,810-0000

660 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6528

Lease Name Griffith Well # 1

Operator: R. J. Patrick

County Seward 199.13

Name & Address P. O. Box 1314

Well Total Depth 6127 feet

Liberál, KS 67901

Conductor Pipe: Size 20" feet 45

Surface Casing: Size 8 5/8 feet 1465'

Well Plugging Notice made out to H & L Operating Co.
Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Midwest Casing Pulling License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: 11:30 am Day: 17 Month: June Year: 19 85

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 4 1/2" at 6126' PBD 5480' Perfs at 5349-5356'

1st plug pump 2 sx hulls and 20 sx cement to bottom

Spot through 4 1/2" casing with mud between plugs

2nd plug at 1500' with 40 sx cement

3rd plug at 780' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' Plugging Proposal Received by Richard W. Lacey

cement to surface with 10 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:00 pm Day: 17 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement to bottom, 2nd plug

at 1500' with 40 sx cement, 3rd plug at 780' with 40 sx cement, 4th & 5th plugs - solid

bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1985

CONSERVATION DIVISION

Wichita, Kansas

Remarks: Recovered 2833' 4 1/2" casing. Used Common Cement by Midwest.

(If additional description is necessary, use BACK of this form.)

INVOICED

(Do not) observe this plugging.

DATE 6-24-85

Signed Paul A. Luthin (TECHNICIAN)

INV. NO. 8678 JUL 18 1985

6-17