

1 020063

FEB 18 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,638-0000
C SE/4, SEC. 6, T 35 S, R 31 W/E
1320 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Lofland "A" Well # 1

Operator: Anadarko Petroleum Corporation
Name &
Address P.O. Box 351
Liberal, KS 67901

County Seward 214.18

Well Total Depth 6590 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1653

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 12:30 p.m. Day: 17 Month: 2 Year: 19 87

Plugging proposal received from Bob Sargent

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 6110' PBTB 6017' Perfs at 5380-90' Anhydrite 1647-57'

1st plug pump down 5 sx cement, 1/2 sx hulls, 10 sx cement, release 4 1/2" wiper plug and displace to 5200'

2nd plug pump 30 sx cement at casing cut off, 3rd plug at 1700' with 50 sx cement,

4th plug at 600' with 30 sx cement, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Don Ubel
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 18 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pump 25 sx cement at perfs,

2nd plug pump 30 sx cement at 3000 feet,

3rd plug pump 50 sx cement at 1700',

4th plug pump 30 sx cement at 600',

5th plug pump 10 sx cement at 0-40'. Heavy mud between plugs...

STATE CORPORATION COMMISSION

2-25-87 FEB 25 1987

Remarks: Used common cement by Sargent's. Recovered 3030' of 4 1/2" casing. CONSERVATION DIVISION
(If additional description is necessary, use BACK of this form.) Wichita, Kansas

INVOICED
observe this plugging.

DATE 2-26-87

Signed Glen R. Barlow
(TECHNICIAN)

INV. NO. 16201
2-18

MAR 27 1987

FORM CP-2/3
Rev. 01-84