

1100299

TO: STATE CORPORATION COMMISSION

6-28

API NUMBER 15-175-20,024-0000
SW NW SEC. 2, T 35 S, R 31 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME PAUL LOUDERBACK WELL # 1-2

TECHNICIAN'S PLUGGING REPORT

COUNTY SEWARD 198.25

OPERATOR LICENSE # 30161

WELL TOTAL DEPTH 6100 FEET

OPERATOR: R.C. TAYLOR COMPANIES PRODUCTION CSG: SIZE 2 7/8" @ 6077' WITH 150SX

NAME AND ADDRESS 501 WEST I-44, SUITE 590 SURFACE CASING: SIZE 8 5/8" @ 1440' WITH 605SX

ADDRESS OKLAHOMA CITY, OK 73118

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER NA

ADDRESS PO BOX 628, GREAT BEND, KS 67530-0628

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 28 MONTH: 06 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM HAROLD FRAULI

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: PERFS AT 5948-78

RUN TUBING. 1ST PLUG AT 1480 WITH 50 SX CEMENT. 2ND PLUG AT 600' WITH 40 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:00 AM DAY: 28 MONTH: 06 YEAR: 1999

ACTUAL PLUGGING REPORT

RUN TUBING TO 1480'. 1ST PLUG SPOT 50 SX CEMENT AT 1480' THROUGH TUBING. FULL RETURN.

2ND PLUG SPOT 40 SX CEMENT AT 618' THROUGH TUBING. FULL RETURN. STATE CORPORATION COMMISSION

3RD PLUG SPOT 10 SX CEMENT AT 40'-0'.

RECEIVED
JUL - 8 1999
7-8-99
CONSERVATION DIVISION
Wichita, Kansas

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. CASING RECOVERED. Rec' 3100

INVOICED

IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.

I (DID) OBSERVE THIS PLUGGING.

DATE 7-9-99

SIGNED Gay Winters (TECHNICIAN) FORM CP-2/3

INV. NO. 60022

AUG 27 1999

6-28