

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21774-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 1-35S-31W
1160 feet from N Section Line, 2140 feet from E Section Line
Lease/Unit Name: RAYMOND Well Number: 1
County: SEWARD Total Vertical Depth: 6400 feet

Operator License No.: 30604
Op Name: RAYDON EXPLORATION, INC.
Address: 9400 N. BROADWAY #400
OKLAHOMA CITY, OK 73114

Conductor Pipe: Size 20 feet: 49
Surface Casing: Size 8.625 feet: 1647 WITH 500 SX CMT
Production: Size 5.5 feet: 6395 WITH 120 SX CMT
Liner: Size _____ feet: _____ 8208.00

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/05/2001 10:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS AND 25 SX CMT ON BOTTOM. 1ST PLUG AT 1680' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/05/2001 3:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 6358'. PERFS AT 6145-6153, 5970-5976'. PUMP 300# HULLS WITH 25 SX CMT TO PLUG PERFS. PRESSURE TO 300#. LOAD HOLE WITH MUD. 1ST PLUG PULL OUT OF HOLE WITH 5 1/2" TO 1680'. LOAD HOLE WITH MUD. PUMP 50 SX CMT. 2ND PLUG PULL OUT OF HOLE WITH 5 1/2" TO 600'. LOAD HOLE WITH MUD. PUMP 40 SX CMT. 3RD PLUG PULL OUT OF HOLE WITH 5 1/2" TO 40' PUMP 10 SX CMT.

RECEIVED
SEP 07 2001
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 5232' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Jim Holland PERT II
(TECHNICIAN)

INVOICED

DATE 9-7-01 SEP 06 2001

INV. NO. 2002060427 MP

Form 0273