

1 020680

6-4

15-175-00021-0001

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-Drill completion date 7/17/58

C SW NE, SEC. 17, T. 35 S, R. 32 W/E

3300 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7123

Lease Name Light Well # 1-17

Operator: H.I. Inc.

County Seward 203.45

Name & Address 110 W. 3rd, P.O. Box 2526

Well Total Depth 6260 feet

Liberal, KS 67905-2526

Conductor Pipe: Size 13 3/8 feet 631

Surface Casing: Size 9 5/8" feet 2496

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 2 p.m. Day: 28 Month: 5 Year: 19 93

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 7" at 6257' w/350 sx cement, PBTD 6223', Perfs at 4547-59, 5226-32'

1st plug pump 1 sx hulls and 25 sx cement,

2nd plug load hole with mud and pump 40 sx cement at 1600',

3rd plug pump 70 sx cement at 650',

4th plug pump 20 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 6 p.m. Day: 4 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 50 sx cement. Pressured up.

2nd plug loaded hole with mud and pumped 40 sx cement at 1600',

3rd plug pumped 70 sx cement at 650',

4th plug pumped 20 sx cement at 40-0'.

RECEIVED STATE CORPORATION COMMISSION JUN 14 1993

Remarks: Used common cement by Sargent & Horton. Recovered 2600' of 7" & 1114' of 9 5/8" casing.

(If additional description is necessary, use BACK of this form)

INVOICED

(did / xxxxxxx) observe this plugging.

DATE 6-22-93

INV. NO. 37979

Signed Glenn R Barlow (TECHNICIAN)